Indian Standard

CODE OF PRACTICE FOR PERMEABILITY TEST FOR MASONRY DURING AND AFTER CONSTRUCTION

UDC 693.1: 620.192.47: 006.76



Copyright 1985

INDIAN STANDARDS INSTITUTION MANAK BHAVAN, 9 BAHADUR SHAH ZAFAR MARG NEW DELHI 110002

Gr 2

October 1985

Indian Standard

CODE OF PRACTICE FOR PERMEABILITY TEST FOR MASONRY DURING AND AFTER CONSTRUCTION

Dams (Overflow and Non-overflow) Sec	ectional Committee, BDC 5	3
--------------------------------------	---------------------------	---

Chairman Representing SHRI V. B. Patel Irrigation Department, Government of Gujarat, Gandhinagar Members SHRI R. K. BHASIN Bhakra Beas Management Board, Nangal Township SHRI J. S. KHURANA (Alternate) PROF M. C. CHATURVEDI Indian Institute of Technology, New Delhi Irrigation Department, Government of Punjab, CHIEF ENGINEER, THEIN DAM Chandigarh DESIGN DIRECTOR (DAM), THEIN DAM DESIGN (Alternate) SHRI C. ETTY DARWIN In personal capacity (P. O. Muttada, Trivandrum) DIRECTOR Public Works Department, Government of Tamil Nadu, Madras SUPERINTENDING ENGINEER (DESIGNS) (Alternate) Central Water & Power Research Station, Pune DIRECTOR JOINT DIRECTOR (Alternate) DIRECTOR (E & RDD-I) Central Water Commission, New Delhi DEPUTY DIRECTOR (E & RDD-I) (Alternate) SHRI M. V. S. IYENGAR Hindustan Construction Co Ltd, Bombay Central Water Commission, New Delhi SHRI K. MADHAVAN DIRECTOR (C & MDD-I) (Alternate) OFFICER ON SPECIAL DUTY Irrigation Department, Government of Andhra Pradesh, Hyderabad SUPERINTENDING ENGINEER (DESIGNS) (Alternate) SHRI RAMABHADRAN NAIR Kerala State Electricity Board, Trivandrum SHRI T. RANGANNA Karnataka Power Corporation Limited, Bangalore REPRESENTATIVE Institution of Engineers (India), Calcutta Central Board of Irrigation & Power, New Delhi SECRETARY DIRECTOR (CIVIL) (Alternate)

(Continued on page 2)

© Copyright 1985 INDIAN STANDARDS INSTITUTION

This publication is protected under the *Indian Copyright Act* (XIV of 1957) and reproduction in whole or in part by any means except with written permission of the publisher shall be deemed to be an infringement of copyright under the said Act.

IS: 11216 - 1985

(Continued from page 1)

Members Representing ENGINEER Irrigation Department, Government of Gujarat, SUPERINTENDING Gandhinagar (CDO) UNIT LEADER (C) (Alternate) SUPERINTENDING ENGINEER (MD) Irrigation Department, Government of Maharashtra, Bombay Director General, ISI (Ex-officio Member) CDO SHRI G. RAMAN. Director (Civ Engg)

Secretary Shri K. K. Sharma Deputy Director (Civ Engg), ISI

Masonry and Concrete Dams Subcommittee, BDC 53:1

Convener

DR B. PANT

Water Resources Development Training Centre, Roorkee

Members

ADDITIONAL CHIEF ENGINEER (DESIGNS)	Irrigation Department, Government of Uttar Pradesh, Lucknow					
DR B. M. AHUJA	Indian Institute of Technology, New Delhi					
SHRI R. K. BHASIN	Bhakra Beas Management Board, Nangal Township					
SHRI K. K. KHOSLA (Alternate)	•					
CHIEF ENGINEER	Irrigation Department, Government of Andhra Pradesh, Hyderabad					
OFFICER-ON-SPECIAL DUTY (Al	ternate)					
SHBI C. ETTY DARWIN	In personal capacity (P. O. Muttada, Trivandrum)					
DIRECTOR (C & MDD-I)	Central Water Commission, New Delhi					
DEPUTY DIRECTOR (C & MDD-	I) (Alternate)					
DIRECTOR (TUNNEL & SPILLWAY)	lrrigation Department, Government of Punjab, Chandigarh					
DIRECTOR/PP (Alternate)	-					
DR A. K. MULLICK SHBI N. K. JAIN (Alternate)	Cement Research Institute of India, New Delhi					
SHRI RAMABHADBAN NAIR	Kerala State Electricity Board, Trivandrum					
SHRI M. P. BHABATHAN (Altern	ate)					
SHRLT, RANGANNA	Karnataka Power Corporation Ltd, Bangalore					
SUPERINTENDING ENGINEER	Irrigation Department, Government of Gujarat, Gandhinagar					
UNIT LEADER (C) (Alternate)	-					
SUPERINTENDING ENGINEER (MD)	Irrigation & Power Department, Government of Maharashtra, Bombay					
SHRI P. R. TONGONKAR	In personal capacity (Shirish Co-operative Housing Society, Bombay)					

Indian Standard

CODE OF PRACTICE FOR PERMEABILITY TEST FOR MASONRY DURING AND AFTER CONSTRUCTION

0. FOREWORD

0.1 This Indian Standard was adopted by the Indian Standards Institution on 14 February 1985, after the draft finalized by the Dams (Overflow and Non-overflow) Sectional Committee had been approved by the Civil Engineering Division Council.

0.2 Masonry is being adopted as a standard material of construction for low as well as high gravity dams. One of the important characteristics of a construction material for water retaining structures is impermeability.

0.3 It is the common practice to specify the strength requirements of mortar in masonry dams. In addition, an upper limit of permeability for mortar and masonry in masonry dams is required to be specified with a view to achieving a standard of workmanship.

0.4 Varying standards have been used for testing masonry in various masonry dams with regard to their permeability. Hence a need was felt for rationalizing a standard criterion for the same.

0.5 For the purpose of deciding whether a particular requirement of this standard is complied with, the final value, observed or calculated, expressing the result of a test, shall be rounded off in accordance with IS: 2-1960*. The number of significant places retained in the rounded off value should be the same as that of the specified value in this standard.

1. SCOPE

1.1 This code gives guidelines for permeability tests for masonry during and after construction and the standards to be achieved.

^{*}Rules for rounding off numerical values (revised).

2. DEFINITIONS

2.1 Coefficient of Permeability — The rate of flow of water under laminar flow conditions through a unit cross-sectional area of porous medium under a unit hydraulic gradient and at a standard temperature of 27°C.

2.2 Lugeons — It is the water loss in litres per minute per metre depth of the drill hole under a pressure of 10 atmospheres maintained for 10 minutes in a drill hole of 46 to 76 mm diameter.

3. PERMEABILITY TESTS

3.1 Frequency of Test

3.1.1 Masonry — Permeability test for the masonry shall be conducted regularly and at frequent intervals to judge quality and maintain uniformity. Every block, where fresh masonry is laid, shall be tested at least once every year.

3.1.2 Mortar — Permeability tests on mortar shall normally be carried out once in a week. Specimens 100 mm dia and 50 mm high or similar size prepared from mortar as used on work shall be used for testing.

3.2 Testing Procedure for Masonry -- Test holes 76 mm in diameter and of appropriate depth (say 4 to 6 m) shall be drilled on the built up masonry after 28 days hardening. Drilling by rotary (diamond) drill shall be preferred in order to have the least disturbance of the masonry already constructed. The holes shall be kept 300 to 600 mm above the bottom level of the masonry to be tested. These holes shall be drilled vertically in two rows. One row shall be at 1.5 m from the axis of the dam. The second row shall be at about one-third of the width of the dam from the rear face excluding the front impervious face. The holes shall be provided staggered and it should be seen that at least one hole each in upstream and downstream portion in each block is provided. The holes may be closer if found necessary on the basis of the permeability test results. In locating the holes, position of any embedded parts, instruments, galleries and other opening shall be kept in view. The holes thus drilled shall be cleaned, filled with water and saturated for 48 hours. Then these holes shall be subjected to a water loss test to determine 'Lugeon' value. Notwithstanding the test pressures specified for lugeon values, the actual test pressures should not be so high as to cause disturbance to masonry. Then assuming linear variation of water loss with respect to the pressure applied, the water loss in lugeons may be interpreted. For details of procedure and test equipment reference may be made to IS : 5529 (Part 2)-1973*.

^{*}Code of practice for in-situ permeability tests: Part 2 Test in bedrock.

3.2.1 When a concrete membrane is used on the upstream face of a masonry dam, the upstream hole for water loss test shall be drilled one meter downstream of the junction of concrete membrane with masonry.

3.2.2 After the water loss tests the holes shall be grouted to refusal with neat cement and the results of grout intake recorded.

3.3 Testing Procedure for Mortar – Permeability tests on mortar specimen shall be conducted in accordance with the procedure specified in IS: 1727-1967*.

4. STANDARDS OF IMPERMEABILITY

4.1 Masonry — Standard of impermeability aimed at shall be a water loss of not more than 2.5 and 5 lugeons in the upstream and downstream portions of the dam respectively.

4.1.1 Permissible water loss in holes drilled in accordance with 3.2.1 shall be not more than 2.5 or 5 lugeons depending on the mortar mix used for masonry at that location (rich or lean respectively).

4.1.2 The values of water loss obtained from the test is the overall value of masonry including loss into cracks joints, etc. It provides an approximate estimate of the possible leakage that may take place through specific zones of masonry.

4.2 Mortar — Mortar as used on work shall not give a coefficient of permeability greater than 2.5×10^{-8} mm/s for rich mortar and 4.8×10^{-8} mm/s for lean mortar.

5. FACTORS AFFECTING PERMEABILITY

5.1 Two factors affecting permeability of the masonry are:

- a) permeability of mortar itself; and
- b) workmanship, namely, whether voids between the stones are filled with mortar or left free.

5.2 Pointing in the upstream face reduces seepage through the dam.

6. REMEDIAL MEASURES

6.1 If the test results indicate water loss greater than specified values grouting should be done as a remedial measure. Grouting pressure should be kept such that it does not damage the constructed masonry.

^{*}Methods of test for pozzolanic material (first revision).

INDIAN STANDARDS

ON

DAMS

IS:

6512-1984	Criteria for	design	of solid	gravity	dams	(first revision))
-----------	--------------	--------	----------	---------	------	------------------	---

- 6955-1973 Code of practice for subsurface exploration for earth and rockfill dams
- 7894-1975 Code of practice for stability analysis of earth dams
- 8237-1976 Code of practice for protection of slope for reservoir embankments
- 8414-1977 Guidelines for design of under-seepage control measures for earth and rockfill dams
- 8605-1977 Code of practice for construction of masonry in dams
- 8826-1978 Guidelines for design of large earth and rockfill dams
- 9296-1979 Guidelines for inspection and maintenance of dams and appurtenant structures
- 9297-1979 Recommendations for lighting, ventilation and other facilities inside dams
- 9429-1980 Code of practice for drainage system for earth and rockfill dams
- 10135-1982 Code of practice for drainage system for gravity dams
- 10635-1983 Guidelines for free board requirement in embankment dams