Indian Standard

METHODS OF TEST FOR AUTOCLAVED CELLULAR CONCRETE PRODUCTS PART I DETERMINATION OF UNIT WEIGHT OR BULK DENSITY AND MOISTURE CONTENT

(Fourth Reprint NOVEMBER 1994)

UDC 666.973.6:531.75

© Copyright 1972

BUREAU OF INDIAN STANDARDS MANAK BHAVAN, 9 BAHADUR SHAH ZAFAR MARG NEW DELHI 110002

Indian Standard

METHODS OF TEST FOR AUTOCLAVED CELLULAR CONCRETE PRODUCTS

DETERMINATION OF UNIT WEIGHT OR BULK PART 1 DENSITY AND MOISTURE CONTENT

Cement and Concrete Sectional Committee, BDC 2

Chairman

R H. C. VISVESVARAYA

Members

R A. S. BHADURI SHEI E. K. RAMACHANDRAN (Alternate)

IRI A. K. CHATTERJI

DR S. S. REHSI (Alternate) BECTOR

DR R. K. GHOSH (Alternate) RECTOR (CSMRS)

DEPUTY DIRECTOR (CSMRS) (IBI K. C. GROSAL

SHRI A. K. BISWAS (Alternate)

R. K. GHOSH

R R. R. HATTIANGADI

SHRI P. J. JAGUS (Alternate) MINT DIRECTOR, STANDARDS

(B&S) DIRECTOR. DEPUTY

STANDARDS (B & S) (Alternate) HRI S. B. JOSHI HRIM T. KANSE

HRI KARTIK PRASAD SHRI S. L. KATHURIA (Alternate)

HRIS, R. KULKARNI HRIM, A. MENTA HRI O. MUTHACHEN

SUPERINTENDING ENGINEER. 2ND CIRCLE (Alternate)

HRI ERACH A. NADIRSHAH

HRI K. K. NAMBIAR

Representing

Cement Research Lastitute of India, New Delhi

National Test House, Calcutta

Central Building Research Institute (CSIR), Roorkee

Central Road Research Institute (CSIR). New Delhi

Central Water & Power Commission, New Delhi

Alternate)

Alokudyog Services Ltd. New Delhi

Indian Roads Congress, New Delhi Associated Cement Companies Ltd. Bombay

Research, Designs & Standards Organization Lucknow

S. B. Joshi & Co Ltd, Bombay Directorate General of Supplies & Disposals Roads Wing, Ministry of Transport & Shipping

M. N. Dastur & Co (Private) Ltd, Calcutta Concrete Association of India, Bombay Central Public Works Department

Institution of Engineers (India), Calcutta In personal capacity (Ramanalaya , 11 First Crescent Park Road, Gandhingear, Advar, Medras

(Continued on page 2)

IS: 6441 (Part I) - 1972

(Continued from page 1)

Memhers

Representing

BRIG NARESH PRASAD COLJ. M. TOLANI (Alternate)

PROF G. S. RAMASWAMY

Engineer-in-Chief's Branch, Army Headquarters

Structural Engineering Research Centre (CSIR Roorkee

DR N. S. BHAL (Alternate)

DR A. V. R. RAO SHRI RAVINDER LAL (Alternate)

SHRI G. S. M. RAO

SHRI T. N. S. RAO

SHRI S. R. PINHEIRO (Alternate) SECRETARY

SHRI R. P. SHARMA

SHRI MOHINDER SINGH (Alternate) SHRI G. B. SINGH

SHRI C. L. KASLIWAL (Alternate)

SHRI J. S. SINGHOTA SHRI A. M. SINGAL (Alternate)

SHRI K. A. SUBRAMANIAM

SHRI T. S. RAMACHANDRAN (Alternate) SHRI L. SWAROOP

SHRI A. V. RAMANA (Alternate) SHRI D. AJITHA SIMHA. Director (Civ Engg.)

National Buildings Organization, New Delhi

Geological Survey of India, Nagpur Gammon India Ltd, Bombay

Central Board of Irrigation & Power, New Delhi Irrigation & Power Research Institute, Amritsar

Hindustan Housing Factory Ltd, New Delhi

Beas Designs Organization, Nangal Township India Cements Ltd. Madras

Dalmia Cement (Bharat) Ltd, New Delhi Director General, ISI (Ex-officio Member)

Secretary

SHRI Y. R. TANEJA Deputy Director (Civ Engg), ISI

Precast Concrete Products Subcommittee, BDC 2:9

Convener

SHRI M. A. MEHTA

Concrete Association of India, Bombay

Neyveli Lignite Corporation Ltd, Neyveli

Members

SHRI E. T. ANTIA (Alternate to Shri M. A. Mehta)

SHRI V. A. ARTHANOOR

SHRIT RAMACHANDRAN (Alternate) SHRI H. B. CHATTERJEE

SHRI S. K. CHATTERJEE DEPUTY DIRECTOR, STANDARDS

(B&S)

Assistant Director, Stand-ARDS (M/C) (Alternate)

DIRECTOR (CSMRS) DEPUTY DIRECTOR (CSMRS) (Alternate)

Hindustan Block Manufacturing Co Ltd, Calcutta Hindustan Housing Factory Ltd, New Delhi

Research, Designs & Standards Organization Lucknow

Central Water & Power Commission, New Delhi

(Continued on page

Indian Standard

METHODS OF TEST FOR AUTOCLAVED CELLULAR CONCRETE PRODUCTS

PART I DETERMINATION OF UNIT WEIGHT OR BULK DENSITY AND MOISTURE CONTENT

0. FOREWORD

- .1 This Indian Standard (Part I) was adopted by the Indian Standards astitution on 21 February 1972, after the draft finalized by the Cement and Concrete Sectional Committee had been approved by the Civil angineering Division Council.
- .2 Autoclaved cellular concrete is a class of material, which has been eveloped commercially abroad and is in the process of development in his country also. A series of Indian Standards on cellular concrete is eing formulated so as to provide guidance in obtaining reliable products autoclaved cellular concrete. The Sectional Committee has considered the desirable to issue a standard for the methods of test for autoclaved cellular concrete products for the guidance of manufacturers and users.
- 1.3 In the formulation of this standard due weightage has been given to nternational co-ordination among the standards and practices prevailing n different countries in addition to relating it to the practices in the field n this country.
- 1.4 For convenience of reference, 'Indian Standard methods of test for utoclaved cellular concrete products' has been grouped into the following nine parts:
 - Part I Determination of unit weight or bulk density and moisture content
 - Part II Determination of drying shrinkage
 - Part III Determination of thermal conductivity
 - Part IV Corrosion protection of steel reinforcement in autoclaved cellular concrete
 - Part V Determination of compressive strength
 - Part VI Strength, deformation and cracking of flexural members subject to bending-short duration loading test

IS: 6441 (Part I) - 1972

Part VII Strength, deformation and cracking of flexural members subject to bending-sustained loading test

Part VIII Loading tests for flexural members in diagonal tension Part IX Jointing of autoclaved cellular concrete elements

0.5 In reporting the result of a test made in accordance with this standard, if the final value, observed or calculated, is to be rounded off, it shall be done in accordance with IS: 2-1960*.

1. SCOPE

- 1.1 This standard (Part I) covers the methods . determining the following:
 - a) Unit weight or bulk density of autoclaved cellular concrete products, determined as the ratio between the weight of the specimen after drying at 105°C and volume of the specimen; and
 - b) Moisture content of autoclaved cellular concrete products.

2. TEST SPECIMENS

2.1 Shape of Specimens— The bulk density and moisture content shall be determined on regularly shaped specimens (without reinforcement) with a minimum thickness of 50 mm. The two large surjeces of the specimen located opposite each other shall have a surface area f atleast 20000 mm² each and the length of the edge shall not be less than 100 mm.

Note 1 — A specimen of size $100 \times 200 \times 50$ mm will meet the above requirements.

NOTE 2 — Whenever feasible, the specimens used for determination of bulk density and moisture content, and the specimen for determination of compressive strength should be cut from the same sample of cellular concrete product.

- 2.2 Location of Specimens From eac's sample for which the density is to be determined, three test specimens shall be taken, and these shall form the test series. One specimen shall be taken from the upper third of the sample, one from the middle and one from the lower section. The position of the specimen is with reference to the direction of rise in aerated concrete mass during manufacture.
- 2.2.1 It is permissible to prepare the specimens from items which have previously been used for other tests provided the specimens are not cut within a distance of atleast 15 cm from an area where visible damage or changes in the normal structure and appearance have occurred. The specimens shall not contain any reinforcement.

^{*}Rules for rounding off numerical values (revised).

1.3 Preparation of Specimens — The specimens shall be cut by rotating carborundum blades or similar device. All surfaces shall be clean cut and plane. The largest surface shall not deviate from planeness by more than 0.1 mm, if measured diagonally with a straight-edge.

3. APPARATUS

- 3.1 Straight-Edge approximately 500 mm long.
- 3.2 Calliper allows readings to an accuracy of 0.1 mm.
- 3.3 Drying Oven for a temperature of $105 \pm 5^{\circ}$ C.
- 3.4 Balance with a weighing accuracy of 0.5 g.

4. PROCEDURE

4.1 Bulk Density

- 4.1.1 Measurement of Specimens Length, width and thickness shall be measured before drying at 105°C with an accuracy of 0·1 mm using a suitable calliper. These measurements shall permit the determination of the volume V of the specimen with an error not exceeding one percent.
- 4.1.2 Drying of Specimens After measuring, the specimens shall be placed in a drying oven at $105 \pm 5^{\circ}$ C until all moisture has been removed and constant weight is obtained. Immediately after removing from the drying oven, the specimens shall be weighed (see Note). The weighing error shall not exceed 0.1 percent of the weight of the specimen. The weight W of the specimen shall be considered constant if the weight after four hours further drying has not changed more than 0.2 percent.
 - Note To facilitate handling, the specimen after removal from the oven, may be cooled to room temperature in a suitable desiccator and weighed immediately.

4.2 Moisture Content

- **4.2.1** Weighing of Specimens The specimen as in **4.1.1** (or immediately after loading, in case the moisture content is to be determined for compressive strength specimens (see 1.1 and 2.1), shall be weighed. The weighing error shall not exceed 0.1 percent. This weight shall be designated W_1 .
- 4.2.2 After weighing, the specimen shall be dried out at $105 \pm 5^{\circ}$ C as in 4.1.2 until constant weight is obtained within a duration of four hours.

15:6441 (Part I) - 1972

Immediately after removing from the drying oven, the specimen shall be weighed (if necessary by cooling to room temperature in a suitable desiccator), and weight W obtained as in 4.1.2.

5. CALCULATIONS

5.1 The bulk density γ in g/cm³ shall be calculated as follows:

$$\gamma = \frac{W}{V} (g/cm^3)$$

where

W = dry weight of the specimen in g, and

 $V = \text{volume in cm}^3$.

- 5.1.1 Bulk density of the individual specimens shall be calculated and reported within the three decimal places, the mean value of the three specimens shall be within two decimal places.
- **5.2** Moisture content F in weight, percent of the dry material, shall be determined as follows:

$$F = \frac{W_1 - W}{W} \times 100 \text{ (percent)}$$

where

 $W_1 = \text{sampled weight of the specimen in g, and}$

W = dry weight of the specimen in g.

5.2.1 Moisture content of individual specimen shall be stated in whole percent, and the mean value of three specimens shall also be stated in whole percent.

6. REPORT

- 6.1 The report shall include the following:
 - a) Code designation;
 - b) Identification of product;
 - c) Date of manufacture;
 - d) Place, method and time of sampling;
 - e) Bulk density of each specimen and mean value of test series; and
 - f) Moisture content of each specimen and mean value of test series.

Continued from page 2)

Members

Representing Alokudvog Services Ltd, New Delhi

SHRI K. C. GHOSAL SHRI A. K. BISWAS (Alternate)

SHRI M. K. GUPTA

SHRI B. K. JINDAL

SHRI B. D. JAYARAMAN

Himalayan Tiles & Marble Pvt Ltd, Bombay

State Housing Board, Madras Central Building Research Institute (CSIR) Roorkee

DR S. S. REHSI (Alternate)

SHRI L. C. LAI SHRI G. C. MATHUR In personal capacity (B/17, West End, New Delhi 23) National Buildings Organization, New Delhi

Assistant Director (Designs) (Alternate) Engineering Construction Corporation Ltd, Madras

SHRI S. NAHAROY

SHBI A. RAMAKRISHNA (Alternate) SHRI K. K. NAMBIAR

In personal capacity ('Ramanalaya', 11 Crescent Park Road, Gandhinagar, Adyar, Madras)

SHRI RADHEY SHIAM SHRI B. G. SHIRKE

Engineer-in-Chief's Branch, Army Headquarters B. G. Shirke & Co, Poona

SHRI R. A. DESHMUKH (Alternate)

SHRI C. N. SRINIVASAN SHRI C. N. RAGHAVENDRAN (Alternate)

SURVEYOR OF WORKS (I) DR H. C. VISVESVARAYA

Ć. R. Naravana Rao, Madras

Central Public Works Department Cement Research Institute of India, New Delhi

BUREAU OF INDIAN STANDARDS

	Headquarters:	
	Manak Bhavan, 9 Bahadur Shah Zafar Marg, NEW DELHI 110002	
	Telephones: 331 01 31	legrams : Manaksans
	331 13 75	(Common to all Offic
	Regional Offices:	Telepho
	Central : Manak Bhavan, 9, Bahadur Shah Zafar Marg NEW DELHI 110002	(331 01 2 331 13
*	Eastern : 1/14 C.I.T. Scheme VII M, V.I.P. Road, Maniktola, CALCUTTA 700054	37 86
	Northern: SCO 445-446, Sector 35-C, CHANDIGARH 1600	36 218
	Southern : C.I.T. Campus, IV Cross Road, MADRAS 600113	
T	Western : Manakalaya, E9 MIDC, Marol, Andheri (East), BOMBAY 400093	6 32 92
	Branch Offices:	
ŧ	'Pushpak', Nurmohamed Shaikh Marg, Khanpur, AHMADAB, Peenya Industrial Area, 1st Stage, Bangalore-Tumkur Road, BANGALORE, ECOPES	AD 380001 2 63 39 49
	BANGALORE 560058 Gangotri Complex, 5th Floor, Bhadbhada Road, T.T. Nagar BHOPAL 462003	55 40
	Plot No. 82/83, Lewis Road, BHUBANESHWAR 751002	5 36
	Kalai Kathir Building, 6/48-A Avanasi Road, COIMBATORI	641037 2 67
	Quality Marking Centre, N.H. IV, N.I.T., FARIDABAD 121 Savitri Complex, 116 G. T. Road, GHAZIABAD 201001	001 — 8-71 19
	53/5 Ward No. 29, R.G. Barua Road, 5th By-lane,	3 31
	GUWAHATI 781003	
	5-8-56C L. N. Gupta Marg, (Nampally Station Road) HYDERABAD 500001	23 10
	R14 Yudhister Marg, C Scheme, JAIPUR 302005	6 34
	117/418 B Sarvodaya Nagar, KANPUR 208005	21 68
	Plot No. A-9, House No. 561/63, Sindhu Nagar, Kanpur F LUCKNOW 226005	
	Patliputra Industrial Estate, PATNA 800013	6 23
	District Industries Centre Complex, Bagh-e-Ali Maidan. SRINAGAR 190011	_
	T. C. No. 14/1421, University P. O., Palayam, THIRUVANANTHAPURAM 695034	6 21
	Inspection Offices (With Sale Point):	
	Pushpanjali, First Floor, 205-A West High Court Road. Shankar Nagar Square, NAGPUR 440010	52 51
	Institution of Engineers (India) Building, 1332 Shivaji Nac PUNE 411005	par. 5 24
	*Sales Office Calcutta is at 5 Chowringhee Approach, P. O. Princep Street, CALCUTTA	27 68
	† Sales Office is at Novelty Chambers, Grant Road, BOM	
	‡ Sales Office is at Unity Building, Narasimharaja Square BANGALORE	22,39