

IS : 6441 (Part VIII) - 1973

Indian Standard

**METHODS OF TESTS FOR
AUTOCLAVED CELLULAR CONCRETE
PRODUCTS**

**PART VIII LOADING TESTS FOR FLEXURAL MEMBERS
IN DIAGONAL TENSION**

(Third Reprint OCTOBER 1996)

UDC 666.973.6 : 620.174

© *Copyright* 1973

**BUREAU OF INDIAN STANDARDS
MANAK BHAVAN, 9 BAHADUR SHAH ZAFAR MARG
NEW DELHI 110002**

Indian Standard

METHODS OF TESTS FOR AUTOCLAVED CELLULAR CONCRETE PRODUCTS

PART VIII LOADING TESTS FOR FLEXURAL MEMBERS IN DIAGONAL TENSION

Cement and Concrete Sectional Committee, BDC 2

<i>Chairman</i>	<i>Representing</i>
DR H. C. VISVESVARAYA	Cement Research Institute of India, New Delhi
<i>Members</i>	
DR A. S. BHADURI	National Test House, Calcutta
SHRI E. K. RAMACHANDRAN (<i>Alternate</i>)	Central Building Research Institute (CSIR), Roorkee
SHRI A. K. CHATTERJI	Central Road Research Institute (CSIR), New Delhi
DR S. S. REHSI (<i>Alternate</i>)	Central Water & Power Commission, New Delhi
DIRECTOR	Hyderabad Asbestbs Cement Products Ltd, Hyderabad
DR R. K. GHOSH (<i>Alternate</i>)	Alokudyog Services Ltd, New Delhi
DIRECTOR (CSMRS)	Indian Roads Congress, New Delhi
DEPUTY DIRECTOR (CSMRS)	Associated Cement Companies Ltd, Bombay
(<i>Alternate</i>)	Research, Designs & Standards Organization, Lucknow
SHRI K. H. GANGWAL	
SHRI K. C. GHOSAL	S. B. Joshi & Co Ltd, Bombay
SHRI A. K. BISWAS (<i>Alternate</i>)	Directorate General of Supplies & Disposals
DR R. K. GHOSH	Roads Wing, Ministry of Transport & Shipping
DR R. R. HATTIANGADI	M. N. Dastur & Co (Private) Ltd, Calcutta
SHRI P. J. JAGUS (<i>Alternate</i>)	Concrete Association of India, Bombay
JOINT DIRECTOR, STANDARDS (B & S)	Central Public Works Department
DEPUTY DIRECTOR, STANDARDS (B & S) (<i>Alternate</i>)	
SHRI S. B. JOSHI	
SHRI M. T. KANSE	
SHRI S. L. KATHURIA	
SHRI S. R. KULKARNI	
SHRI M. A. MEHTA	
SHRI O. MUTHACHEN	
SUPERINTENDING ENGINEER, 2ND CIRCLE (<i>Alternate</i>)	

(*Continued on page 2*)

© Copyright 1973

BUREAU OF INDIAN STANDARDS

This publication is protected under the *Indian Copyright Act (XIV of 1957)* and reproduction in whole or in part by any means except with written permission of the publisher shall be deemed to be an infringement of copyright under the said Act.

IS : 6441 (Part VIII) - 1973

(Continued from page 1)

<i>Members</i>	<i>Representing</i>
SHRI ERACH A. NADIRSHAH	Institution of Engineers (India), Calcutta
SHRI K. K. NAMBIAR	In personal capacity (' Ramanalaya ', 11 First Crescent Park Road, Gandhinagar, Adyar, Madras)
BRIG NARESH PRASAD	Engineer-in-Chief's Branch, Army Headquarters
COL J. M. TOLANI (Alternate)	
PROF G. S. RAMASWAMY	Structural Engineering Research Centre (CSIR), Roorkee
DR N. S. BHAL (Alternate)	
DR A. V. R. RAO	National Buildings Organization, New Delhi
SHRI RAVINDER LAL (Alternate)	
SHRI G. S. M. RAO	Geological Survey of India, Nagpur
SHRI T. N. S. RAO	Gammon India Ltd, Bombay
SHRI S. R. PINHEIRO (Alternate)	
SECRETARY	Central Board of Irrigation & Power, New Delhi
SHRI R. P. SHARMA	Irrigation and Power Research Institute, Amritsar
SHRI MOHINDER SINGH (Alternate)	
SHRI G. B. SINGH	Hindustan Housing Factory Ltd, New Delhi
SHRI C. L. KASLIWAL (Alternate)	
SHRI J. S. SINGHOTA	Beas Designs Organization, Nangal Township
SHRI T. C. GARG (Alternate)	
SHRI R. K. SINHA	Indian Bureau of Mines, Nagpur
SHRI K. A. SUBRAMANIAM	India Cements Ltd, Madras
SHRI P. S. RAMACHANDRAN (Alternate)	
SHRI L. SWAROOP	Dalmia Cement (Bharat) Ltd, New Delhi
SHRI A. V. RAMANA (Alternate)	
SHRI D. AJITHA SIMHA, Director (Civ Engg)	Director General, ISI (Ex-officio Member)

Secretary

SHRI Y. R. TANEJA
Deputy Director (Civ Engg), ISI

Pre-cast Concrete Products Subcommittee, BDC 2 : 9

Convener

SHRI M. A. MEHTA Concrete Association of India, Bombay

Members

SHRI E. T. ANITA (Alternate to Shri M. A. Mehta)	
SHRI V. A. ARTHANOUR	Neyveli Lignite Corporation Ltd, Neyveli
SHRI T. RAMACHANDRAN (Alternate)	
SHRI H. B. CHATTERJEE	Hindustan Block Manufacturing Co Ltd, Calcutta
SHRI S. K. CHATTERJEE	Hindustan Housing Factory Ltd, New Delhi
DEPUTY DIRECTOR, STANDARDS (B & S)	Research, Designs and Standards Organization, Lucknow
ASSISTANT DIRECTOR, STANDARDS (M/C) (Alternate)	
DIRECTOR (CSMRS)	Central Water & Power Commission, New Delhi
DEPUTY DIRECTOR (CSMRS) (Alternate)	

(Continued on page 7)

Indian Standard
METHODS OF TESTS FOR
AUTOCLAVED CELLULAR CONCRETE
PRODUCTS

**PART VIII LOADING TESTS FOR FLEXURAL MEMBERS
IN DIAGONAL TENSION**

0. FOREWORD

0.1 This Indian Standard (Part VIII) was adopted by the Indian Standards Institution on 22 March 1973, after the draft finalized by the Cement and Concrete Sectional Committee had been approved by the Civil Engineering Division Council.

0.2 Autoclaved cellular concrete is a class of material, which has been developed commercially abroad and is in the process of development in this country also. A series of Indian Standards on cellular concrete is being formulated so as to provide guidance in obtaining reliable products in autoclaved cellular concrete. The Sectional Committee has considered it desirable to issue a standard for the methods of tests for autoclaved cellular concrete products for the guidance of manufacturers and users.

0.3 In the formulation of this standard due weightage has been given to international co-ordination among the standards and practices prevailing in different countries in addition to relating it to the practices in the field in this country.

0.4 For convenience of reference, 'Indian Standard methods of tests for autoclaved cellular concrete products' has been grouped into the following nine parts:

Part I Determination of unit weight or bulk density and moisture content

Part II Determination of drying shrinkage

Part III Determination of thermal conductivity

Part IV Corrosion protection of steel reinforcement in autoclaved cellular concrete

Part V Determination of compressive strength

Part VI Strength, deformation and cracking of flexural members subject to bending-short duration loading test

Part VII Strength, deformation and cracking of flexural members
subject to bending-sustained loading test

Part VIII Loading tests for flexural members in diagonal tension

Part IX Jointing of autoclaved cellular concrete elements

0.5 In reporting the result of a test or analysis made in accordance with this standard, if the final value, observed or calculated, is to be rounded off, it shall be done in accordance with IS : 2-1960*.

1. SCOPE

1.1 This standard (Part VIII) covers the method for the determination and study of the strength deformations and cracking of flexural members such as floor and roof slabs of cellular concrete subjected to diagonal shear loading.

2. TEST SPECIMEN

2.1 Size of the Specimen — The test specimen shall be the full size member as to be actually used in construction satisfying the requirements of the relevant Indian Standard (or the requirements specified by the manufacturer) in respect of shape and dimensions.

2.2 Condition of the Test Specimen

2.2.1 Moisture Content — The moisture content of the concrete during the test should be indicated and should be not less than 10 percent by weight, when determined in accordance with IS : 6441 (Part I)-1972†.

2.2.2 Temperature of Specimen — The temperature of the concrete shall not be materially different from the ambient temperature in which it is being tested and in any case not less than 6°C.


3. TEST ARRANGEMENTS

3.1 The member to be tested shall be simply supported at the ends. The supports shall consist of 25 mm. thick horizontal mild steel plates bedded on rigid supports of steel or concrete. The ends of the member shall be fully in contact with the steel plate over the whole width of the member. The bearing width and the span used for the test shall be the same as

*Rules for rounding off numerical values (revised).

†Methods of test for autoclaved cellular concrete products: Part I Determination of unit weight or bulk density and moisture content.

those indicated by the manufacturer and to be actually used in construction practice (see Fig. 1).



- l = effective span of unit;
- s = steel plate of thickness not less than 25 mm and length equal to width of the unit;
- t = porous fibre board, thickness not less than 12 mm and length equal to width of the unit;
- Q = applied load; and
- h = thickness of element.

FIG. 1 METHOD FOR LOADING TEST FOR CELLULAR CONCRETE FLEXURAL UNITS IN DIAGONAL TENSION

4. LOADING

4.1 A single load shall be applied in the proximity of a support through steel platen not less than 25 mm thick, the load extending over the entire width of the member. The steel platen shall be embedded on soft fibre-board packing, not less than 12 mm thick and of the same plan dimensions as the steel platen. The packing shall be placed between steel loading platen and the top of the member. The width of the steel platen shall not be less than 100 mm and shall be increased, where necessary, in multiples of 50 mm, so that the contact pressure under the applied load is not more than 20 percent of the compressive strength of the concrete. The distance between the axial point of application of the load and the inner edge of the end steel support plate shall be not less than 3 times the depth of the member (see Fig. 1).

4.1.1 The span shall be taken as the distance between the centres of the bearings (see Fig. 1).

4.2 The weight of the loading equipment shall be taken into account in calculating the applied load.

5. MEASUREMENTS

5.1 The loads shall be measured to an accuracy of not less than ± 1.5 percent of the applied load.

5.2 The deflection of the member shall be measured at midspan and the least count of the dial gauge shall be at least 0.01 mm.

5.3 Crack widths shall be measured to an accuracy of ± 0.05 mm.

5.4 The movement of the end of the main tension reinforcement in relation to the concrete shall be measured.

6. TEST PROCEDURE

6.1 Zero for the deflection measurements shall be taken immediately after the member had been placed in position.

6.2 The loading apparatus shall then be fixed, and the load applied gradually at a rate of about 1/4 of the design live load per minute. Measurements shall be taken at suitable intervals. The load at which a diagonal tension crack has appeared shall be maintained for 2 hours. Loading shall then be increased until failure occurs.

7. REPORT

7.1 The test report shall state:

- a) moisture content of the specimen;
- b) temperature of the specimen; and
- c) measured loads, deflections, strains, crack width and movement of the end of main reinforcement for various intervals as in 6.

(Continued from page 2)

<i>Members</i>	<i>Representing</i>
SHRI K. C. GHOSAL	Alokudyog Services Ltd, New Delhi
SHRI A. K. BISWAS (<i>Alternate</i>)	
SHRI V. G. GOKHALE	Bombay Chemicals Private Limited, Bombay
SHRI M. K. GUPTA	Himalayan Tiles & Marble Pvt Ltd, Bombay
SHRI B. D. JAYARAMAN	State Housing Board, Madras
SHRI B. K. JINDAL	Central Building Research Institute (CSIR), Roorkee
DR S. S. REHSI (<i>Alternate</i>)	
SHRI L. C. LAI	In personal capacity (<i>B/17 West End, New Delhi 23</i>)
SHRI G. C. MATHUR	National Buildings Organization, New Delhi
SHRI A. C. GUPTA (<i>Alternate</i>)	
SHRI S. NAHARROY	Engineering Construction Corporation Ltd, Madras
SHRI A. RAMAKRISHNA (<i>Alternate</i>)	
SHRI K. K. NAMBIAR	In personal capacity (<i>'Ramanalaya', 11 First Crescent Park Road, Gandhinagar, Adyar, Madras</i>)
SHRI RADHEY SHIAM	Engineer-in-Chief's Branch, Army Headquarters
SHRI B. G. SHIRKE	B. G. Shirke & Co, Poona
SHRI R. A. DESHMUKH (<i>Alternate</i>)	
SHRI C. N. SRINIVASAN	C. R. Narayana Road, Madras
SHRI C. N. RAGHAVENDRAN (<i>Alternate</i>)	
SURVEYOR OF WORKS (I)	Central Public Works Department
DR H. C. VISVESVARAYA	Cement Research Institute of India, New Delhi

BUREAU OF INDIAN STANDARDS

Headquarters:

Manak Bhavan, 9 Bahadur Shah Zafar Marg, NEW DELHI 110002
Telephones: 323 0131, 323 8375, 323 9402
Fax : 91 11 3234062, 91 11 3239399

Telegrams : Manaksanstha
(Common to all Offices)
Telephone

Central Laboratory :

Plot No. 20/9, Site IV, Sahibabad Industrial Area, Sahibabad 201010

8-77 00 32

Regional Offices:

Central : Manak Bhavan, 9 Bahadur Shah Zafar Marg, NEW DELHI 110002 323 76 17

*Eastern : 1/14 CIT Scheme VII M, V.I.P. Road, Manikola, CALCUTTA 700054 337 86 62

Northern : SCO 335-336, Sector 34-A, CHANDIGARH 160022 60 38 43

Southern : C.I.T. Campus, IV Cross Road, MADRAS 600113 235 23 15

†Western : Manakalaya, E9, Behind Marol Telephone Exchange, Andheri (East), MUMBAI 400093 832 92 95

Branch Offices::

'Pushpak', Nurmohamed Shaikh Marg, Khanpur, AHMEDABAD 380001 550 13 48

‡Peenya Industrial Area, 1st Stage, Bangalore-Tumkur Road, BANGALORE 560058 839 49 55

Gangotri Complex, 5th Floor, Bhadbhada Road, T.T. Nagar, BHOPAL 462003 55 40 21

Plot No. 62-63, Unit VI, Ganga Nagar, BHUBANESHWAR 751001 40 36 27

Kalaikathir Buildings, 670 Avinashi Road, COIMBATORE 641037 21 01 41

Plot No. 43, Sector 16 A, Mathura Road, FARIDABAD 121001 8-28 88 01

Savitri Complex, 116 G.T. Road, GHAZIABAD 201001 8-71 19 96

53/5 Ward No.29, R.G. Barua Road, 5th By-lane, GUWAHATI 781003 54 11 37

5-8-56C, L.N. Gupta Marg, Nampally Station Road, HYDERABAD 500001 20 10 83

E-52, Chitaranjan Marg, C-Scheme, JAIPUR 302001 37 29 25

117/418 B, Sarvodaya Nagar, KANPUR 208005 21 68 76

Seth Bhawan, 2nd Floor, Behind Leela Cinema, Naval Kishore Road, LUCKNOW 226001 23 89 23

Patliputra Industrial Estate, PATNA 800013 26 23 05

T.C. No. 14/1421, University P. O. Palayam, THIRUVANANTHAPURAM 695034 6 21 17

Inspection Offices (With Sale Point) :

Pushpanjali, 1st Floor, 205-A, West High Court Road, Shankar Nagar Square, NAGPUR 440010 52 51 71

Institution of Engineers (India) Building 1332 Shivaji Nagar, PUNE 411005 32 36 35

*Sales Office is at 5 Chowringhee Approach, P.O. Princep Street, CALCUTTA 700072 27 10 85

†Sales Office is at Novelty Chambers, Grant Road, MUMBAI 400007 309 65 28

‡Sales Office is at 'F' Block, Unity Building, Narashimaraja Square, BANGALORE 560002 222 39 71